Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Detailed Estimated for Providing Cement Concrete to Cross Roads at Abbiger Janatha Colony, in Shettyhalli Sub Division. In Ward no. 12

Est .Cost Rs. 9.90 Lakhs

Sl No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB 2-1 2 Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings culverts. road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m excavated surface leveled and neatly dressed disposed earth to be leveled after breaking of clods and neatly dressed as per specifications specification No KBS 2 1(a) / 2 3.1 Page No 5/ Item No 2 2/ PWD SR 2009-10	Cum							
			1	46 00	4 50	0 30	62 10		
			1	70 00	5.00	0 35	122 50		
			1	77 00	4 50	0.35	121 28		
							305.88	127 20	**38907**
	Basic Rate	120.00							
	Area Weightage 6%	7 20							
		127 20							
2	KSRB-2-2 1 Earthwork excavation for foundation of buildings culverts. water supply. sanitary lines and electrical conduits either in pits or in trenches 1 5m and above in width in ordinary soil not exceeding 1 5 m in depth including dressing the bottom and sides of pits and trenches. stacking the excavated soil clear from edges of excavation with lead up to 50 m after breaking of clods complete as per specifications Specification No KBS 2 1(a)/ 2 3 5. Page No 5/ Item No. 2 3/ PWD SR 2009-10	Cum							
	Culverts		2	6.00	2 00	1 20	28 80		
							28.80	109 18	**3144**
	Basic Rate	103.00							
	Area Weightage 6%	6 18							
		109.18							

3	KSRB 4-1 3 Providing and laying in position plain cement concrete of nominal mix 1 4 8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specifications Specification No KBS 4 1 4 2 Page No 12/ Item No 4 3/ PWD SR 2009-10	Cum							
	Culverts		2	6.00	1.80	0.15	3.24		
							3.24	3153 50	**10217**
	Basic Rate	2,975.00							
	Area Weightage 6%	178.50							
		3,153.50							
4	KSRB 5 3-3 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1 6, edges of stones chistle dressed in courses not less than 15 cms high bond stones at two m apart in each course including cost of materials labour curing complete as per specifications KBS 5-1 13 Page No 21/ Item No 5 9/ PWD SR 2009-10	Cum							
	Culverts		2x2	6 00	0 60	0 90	12 96		
							12.96	2776 14	**35978.8**
	Basic Rate	2,619 00							
	Area Weightage 6%	157.14							
		2,776.14							
5	KSRB 4-1 6 Providing and laying in position plain cement concrete of mix 1 2 4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications Specification No KBS 4 1 4 2 Page No 12/ Item No 4 6/ PWD SR 2009-10	Cum							
	Culverts		2x2	6 00	0 60	0 10	0 72		
							0.72	3845 68	**2769**
	Basic Rate	3,939.00							
	Area Weightage 6%	236 34							
		4,175 34							

6	KSRB 15 1 1 Providing flush pointing to square rubble. course or uncoursed stone masonry with cement mortar 1 3 20 mm deep after raking joints to depth of 20mm nicely lining including cost of materials labour curing complete as per specifications Page No 96/ Item No 15 1 / PWD SR 2009-10	Cum							
	Culverts		2x2	6 00		0 90	21 60		
							21.60	57 13	**1234**
	Basic Rate	53 90							
	Area Weightage 6%	3.23							
		57 13							
7	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R C C works laid in 15cms thick layers and well compacted vibrating curing finishing with necessary cement mortar form works and scaffoldings to withstand pumping of concrete with all lead and lifts etc complete (exclusive of cost of steel and fabrication charges ı Ready mixed Cement concrete M-15 (1 2 4) for raft foundation column footing main and secondary beams Page No 17/ Item No 4 48 1/ PWD SR 2009-10	Cum							
	Culverts		2	6 00	1 80	0 23	4 97		
							4.97	4386 28	**21791**
	Basic Rate	4 138 00							
	Area Weightage 6%	248 28							
		4.386.28							
8	KSRB 4 9 2 providing T M T steel reinforcement for R C C work including straightening cutting bending hooking placing in position lapping and / or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials labour HOM of machinery complete as per specifications Specification No KBS 4 6.3 Page No 16/ Item No 4 46/ PWD SR 2009-10	Q							
							4.97	5031 14	**24995**
	Basic Rate	4 697 00							
	Area Weightage 6%	334 14							
		5.031 14							

9	KSRB 4-1 3 Providing and laying in position plain cement concrete of nominal mix 1 4 8 using 40mm and down size graded granite metal machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation and plinth including cost of all materials labour HOM of machinery, curing complete as per specifications Specification No KBS 4 1 4 2 Page No 12/ Item No 4 3/ PWD SR 2009-10	Cum							
			1	46 00	4 50	0 15	31 05		
			1	70 00	5 00	0 15	52 50		
			1	77 00	4 50	0 15	51 98		
							135.53	3153 50	**427378**
	Basic Rate	2,975.00							
	Area Weightage 6%	178 50							
		3 153 50							
10	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R C C works laid in 15cms thick layers and well compacted vibrating curing finishing with necessary cement mortar form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc complete (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete M-15 (1 2 4) for raft foundation column footing main and secondary beams Page No 17/ Item No 4 48 1/ PWD SR 2009-10	Cum							
			1	46 00	4 50	0 10	20 70		
			1	70 00	5 00	0 10	35 00		
			1	77 00	4 50	0 10	34 65		
							90.35	4386 28	**396300**
	Basic Rate	4 138 00							
	Area Weightage 6 %	248 28							
		4 386 28							
11	KSRRB M2600-3 (II) Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per Drawing & Technical Specification Complete as per Specifications MORTH Specification no 2605 Page No 212/ Item No 31.3/ PWD SR 2009-10	m							
				30 00			30 00		
							30.00	130 38	**3911**
	Basic Rate	123 00							
	Area Weightage 6%	7 38							
		130 38							

12	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc complete (P-123)	Cum								
	Qty Vide Item No=1+2							334.68		
	Qty Limited to							327.00	71 34	23328
	Basic Rate	67 30								
	Area Weightage 6%	4 04								
		71 34								
13	Miscellaneous and unforseen Charges									46
									Total	990000

(Rupees Nine Lakhs Ninety thousand Only)

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary
2 The Estimate is prepared as per the PWD SR 2009-10
3 The Provision made in estimate are adequate and essential
4 This area comes under BBMP limits

Asst Engineer
Shettyhalli Sub-Division

S/C Asst Executive Engineer
Shettyhalli Sub-Division
BBMP

Executive Engineer
Dasarahalli Zone
BBMP

ಸಂ. ಇ ಇ/ DDI/ AS/ 48/ 10-11 ದಿನಾಂಕ : 06/08/2010

ರಿ. 9.90 lakhs (Nine lakhs ninety thousand only)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ಸಂ. ಇ ಇ/ DDI/ AS/ 48/ 10-11 ದಿನಾಂಕ : 06/08/2010

ರಿ. 9.90 lakhs (Nine lakhs ninety thousand only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು